



STOCK SINERGY
CIVITERMINAL

TECHNICAL RESOURCE

Terminal Technical Datasheet

A concise public overview of Stock Sinergy Civiterminal current storage infrastructure and bulk-liquid handling platform.

DOCK 24 / PORT OF CIVITAVECCHIA

www.stocksinerogy.it

2026



Terminal at a glance

14,750 t

Current operating storage capacity

19

Stainless-steel storage tanks

6

Dedicated stainless-steel lines

14 m

Draught at Dock 24

Storage & handling

- **Dedicated heating**
Dedicated heating is stated for each storage tank.
- **Transfer infrastructure**
Six dedicated stainless-steel lines connect terminal storage with vessel-linked handling.
- **Measurement**
Electronic tank weight control supports inventory monitoring.
- **Data management**
IBM AS400 GALILEO is stated as the terminal data-management platform.

Quality, safety & control

- **Surveillance**
Internal and remote video surveillance supports continuous terminal monitoring.
- **Perimeter alarm**
The site states perimeter alarm integration with the port authority.
- **Expansion 2026**
Four additional 1,500 t tanks are under construction, adding 6,000 t of planned capacity; completion is planned by the end of 2026.
- **Rail connection**
A rail connection is stated as being in development.

Commercial and technical qualification

Final cargo acceptance, capacity, berth conditions and customs feasibility are confirmed only after product-specific technical, safety, customs and operational review.